

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-22.936-00-00

LEASE NAME Patricia

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

2970 Ft. from S Section Line

990 Ft. from E Section Line

LEASE OPERATOR Palomino Petroleum

SEC. 27 TWP. 17 RGE. 24 (S or W)

ADDRESS P.O. Box 18610

COUNTY Ness

PHONE# 316) 683-8152 OPERATORS LICENSE NO. 5161

Date Well Completed 10-31-85

Character of Well D & A

Plugging Commenced 3:30 AM

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6:30 AM

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1 Dodge City

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation D & A Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4473

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface hole	Sand & Shale	0	250	8 5/8	242	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Plug @ 1774' - 50 sx, plug @ 760' - 80 sx, plug @ 280' - 40 sx, plug @ 40' - 10s  
+ solid bridge, plug @ rathole - 10 sx. 190 sx 60/40 pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DNB Drilling, Inc. License No. 5476

Address 535 N. Oliver Wichita, KS 67208

STATE OF Kansas COUNTY OF Sedgwick, ss.

Bob Watchous (~~Employee of Operator~~) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, s Bob Watchous God.

RECEIVED  
STATE CORPORATION COMMISSION  
12-04-1985  
DEC 4 1985

(Signature) \_\_\_\_\_

(Address) P.O. Box 18610

SUBSCRIBED AND SWORN TO before me this 15<sup>th</sup> day of November, 19 85

CONSERVATION DIVISION  
Wichita, Kansas


Kathryn L. Frerking  
Notary Public

My Commission Expires: August 21, 1989



15-135-22936-00-00

# D N B Drilling, Inc.



J. L. DONELSON, PRES.  
(316) 687-5471

ROTARY CONTRACTOR DRILLING DEALS

535 NORTH OLIVER

WICHITA, KANSAS 67208

## DRILLERS' LOG

Palomino Petroleum  
P.O. Box 18610  
Wichita, KS 67218

#1 Patricia  
SW SE NE Sec. 27-17-24  
Ness County, KS

Commenced: 10-24-85  
Completed: 10-31-85

Surface casing: Ran 6 jts. 8 5/8", 20# new casing. Tallied 241.86',  
set @ 250'. Cemented with 185 sx 60/40 pozmix, 2%  
gel, 3% cc. Cement did circulate.

### FORMATION

Sand & Shale  
Anhydrite  
Shale  
Shale & Lime  
Lime

### DEPTH

0-1742  
1742-1774  
1774-2755  
2755-3950  
3950-4473 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

DNB Drilling, Inc.

By *Jan Paul*

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 5th day of November, 1985.

Vicky L. Coppage, Notary Public

My appointment expires:  
May 28, 1989

*Vicky L. Coppage*

