


15-135-22068-00-00

FORM CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

Ness County. Sec. 27 Twp. 17S Rge. 24W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

200' SW fo NE SE

Lease Owner John Jay Darrah, Jr.

Lease Name Audrey Rufenacht Well No. #1

Office Address Century Plaza Wichita, Kansas 67202

Character of Well (Completed as Oil, Gas or Dry Hole)

Date Well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 8-28-81 19

Plugging completed 9-3-81 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production
Depleted 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation Depth to top Bottom Total Depth of Well 4435'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	306'	none
				4-1/2"	4426'	2486'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Moved in on location, got 8" stretch, ran sand to 4350' and set 4 sacks cement. Shot
and worked pipe ~~XXXXX~~ @3488', 2994' and 2505'. Pulled 62 joints of pipe. Plugged
well with 24 sacks gel, 5 sacks hulls, 8-5/8" plug, 140 sacks 50/50 pos, 4% gel, 3% ce.
Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice
R, Darrell Kelso (employee of owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso

R. Darrell Kelso
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of September, 19 81

My commission expires



Irene Hoover
Notary Public.

15-135-22068-00-00

DRILLERS LOG

COMPANY: JOHN JAY DARRAH, JR.
CONTRACTOR: MALLARD DRILLING CO., INC.
405 Century Plaza
Wichita, Kansas 67202

WELL NAME: AUDREY RUFENACHT
DESCRIPTION:
200' SW of SW NE SE
Section 27-17S-24W

RIG NO.: 1

COUNTY: Ness

TOTAL DEPTH: 4435

ELEVATION: 2406 gr.

COMMENCED: July 23, 1981

COMPLETED: July 29, 1981

CASING RECORD:

8 jts. new 24# 8-5/8" surface casing
111 jts. new 10# 4-1/2" production casing

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil, shale with sand	0	1724	Ran 297' new 24# 8-5/8" surface casing; set at 306' with landing joint, 175 sacks 60/40 pozmix, 3% d.c., 2% gel. Cement circulated. Plug down at 11:45 p.m., July 23, 1981.
Anhydrite	1724	1754	
Shale	1754	3485	
Shale & Shells	3485	3789	
Shale	3789	4130	
Shale & Lime	4130	4325	
Shale	4325	4418	
Shale & TD	4418	4435	Ran 111 jts. new 4 1/2", 10# casing; set with 150 sacks 60/40 pozmix, 2% gel, 10% salt saturated. Set @ 4426'. Job completed at 11:15 p.m., July 29, 1981.

STATE CORPORATION COMMISSION
1772 E. 17th St.
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1981
08-30-1981
CONSERVATION DIVISION
Wichita Kansas

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

I, JOHN JAY DARRAH, JR. of MALLARD DRILLING CO., INC., certify that this is a true and correct copy of the log of the A. RUFENACHT #1 well, to the best of my knowledge.

John Jay Darrah, Jr.

John Jay Darrah, Jr., President

SUBSCRIBED AND SWORN to before me this 31st day of July, 1981.

My Commission Expires:
August 25, 1984

Dianne R. Fowler

Dianne R. Fowler, Notary Public