

15-135-20519-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Ness County, Sec. 26 Twp. 17 Rge. 24 (E) W(W)

Location as "NE/CNW/SE/SW" or footage from lines S NE SW

Lease Owner Wichita Iron & Metal

Lease Name Schreiber Well No. 1

Office Address P.O. Box 13021 Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed _____ 19__

Application for plugging approved _____ 19__

Plugging commenced _____ 8/20 1973

Plugging completed _____ 8/24 1973

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4468 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	415	0
				5 1/8"	4460	2999'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand from 4468' to 4440'. Run 5 sacks of cement from 4440' to 4410'.

Pumped 15 sacks gel mud, 80 sacks cement, 5 gel mud & 20 sacks cement to plug well.

RECEIVED
STATE CORPORATION COMMISSION

SEP 5 1973

CONSERVATION DIVISION
Wichita, Kansas

09-05-1973

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn's Pipe Pulling Co.

Address Box 156 Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

RAY STEKOLL

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ray Stekoll

Box 15021 - Wichita, Kansas 67213

(Address)

SUBSCRIBED AND SWORN to before me this 4th day of September, 1973

My Commission expires July 27, 1975.

Wilma Ritter,
Notary Public.

Notary Public.



15-135-20519-00-00

DRILLERS LOG

SCHREIBER NO. 1

CASING RECORD:	OPERATOR:	Coin Petroleum Company & Circle Oil Company, Inc.	DESCRIPTION:
8-5/8" @ 415'			C NE SW
w/250 sax cement	CONTRACTOR:	Sage Drilling Co., Inc.	Sec. 26-17S-24W
			Ness Co., Kans.
TOTAL DEPTH:	COMMENCED:	November 23, 1971	
4468'	COMPLETED:	December 4, 1971	ELEVATION:
			2443KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	415	
Shale	415	1310	
Sand & Shale	1310	1737	
Anhydrite	1737	1774	
Shale & Lime	1774	2190	
Shale	2190	2415	
Lime & Shale	2415	3785	
Lime	3785	3915	
Lime & Shale	3915	3965	
Lime	3965	4410	
Lime, Shale & Sand	4410	4441	
Lime	4441	4468	5 1/2" @ 4460' w/100 sax cement

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By John R. Bartholomew

Subscribed and sworn to before me this 8th day of December, 1971.



Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1973 06-29-1973

CONSERVATION DIVISION
Wichita, Kansas