

15-135-21536-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 26 Twp. 17S Rge. 24W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C SW SW


Lease Owner Beren Corporation
Lease Name Schreiber Well No. #1
Office Address 970 Fourth Financial Center, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date Well completed November 21, 1978 19
Application for plugging filed November 21, 1978 19
Application for plugging approved November 21, 1978 19
Plugging commenced November 21, 1978 19
Plugging completed November 21, 1978 19
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4476'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 720', 20 sacks @ 300', hulls and 10 sacks @ 40'. Plugging completed at 4:15 a.m., November 21, 1978.

RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1978

11-29-1978
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company


STATE OF KANSAS COUNTY OF BARTON, ss.
Kenneth J. Link (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of November, 1978.

Loneita Barry
Loneita Barry Notary Public.

My commission expires 3-28-80.



15-135-21536-00-00

D R I L L E R S L O G

Schreiber #1

CASING RECORD: 8 jts. used 8-5/8" surface casing	COMPANY: Beren Corporation	DESCRIPTION: C SW SW Section 26-17S-24W Ness County, Kansas
	CONTRACTOR: Strata Drilling Company	
TOTAL ROTARY DEPTH: 4476'	COMMENCED: November 10, 1978	
	COMPLETED: November 21, 1978	

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post rock, shale	0	345	Ran 330' used 8-5/8" surface casing, set and cemented at 335' with 150 sacks 60-40 pozmix, 50 sacks common, cement, 2% gel, 3% C.C. Cement circulated. Plug down @ 2:30 a.m., November 11, 1978.
Shale and sand, shale	345	1742	
Anhydrite	1742	1776	
Shale	1776	2215	
Lime and shale	2215	2940	
Lime	2940	3185	
Lime and shale	3185	4095	
Lime	4095	4195	
Lime and shale	4195	4296	
Lime	4296	4350	
Lime and shale	4350	4415	Ran 6 drill stem tests.
Lime	4415	4476	
			Ran 2 electric logs.
			Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 720', 20 sacks @ 300', hulls and 10 sacks @ 40'. Plugging completed at 4:15 a.m., November 21, 1978.

STATE OF KANSAS)
) ss
 COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY


Kenneth J. Link

 Kenneth J. Link, President

Sworn to and subacribed before me this 27th day of November, 1978,
 My appointment expires 3-28-80.

Loneita Barry

 Loneita Barry, Notary Public



RECEIVED
 STATE CORPORATION COMMISSION
 NOV 29 1978
 11-29-1978
 CONSERVATION DIVISION
 Wichita, Kansas