

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ness County, Sec. 26 Twp. 17S Rge. 24W E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
C NW NW


Lease Owner Beren Corporation  
Lease Name Schreiber A Well No. #1  
Office Address 970 Fourth Financial Center, Wichita, Kansas  
Character of Well (Completed as Oil, Gas or Dry Hole)  
dry hole

Date Well completed December 14, 1978 19  
Application for plugging filed December 14, 1978 19  
Application for plugging approved December 14, 1978 19  
Plugging commenced December 14, 1978 19  
Plugging completed December 14, 1978 19  
Reason for abandonment of well or producing formation  
dry hole

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 4520'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above  
Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set. Hole plugged with 50-50 pozmix, 6% gel, as follows:  
70 sacks @ 720', 20 sacks @ 240', hulls and 10 sacks @ 40'. Plug down @ 11:15 p.m., December 14, 1978.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 20 1978

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company 12-26-1978

STATE OF KANSAS COUNTY OF BARTON, ss.  
Charles W. Steincamp (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp  
P. O. Box 355, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of December, 1978.

Loneita Barry  
Loneita Barry Notary Public.

My commission expires 3-28-80



15-135-21540-00-00

D R I L L E R S   L O G

Schreiber A #1

CASING RECORD:  
7 jts. used 8-5/8"  
surface casing

COMPANY: Beren Corporation  
CONTRACTOR: Strata Drilling Company

DESCRIPTION: C NW NW  
Section 26-17S-24W

TOTAL ROTARY  
DEPTH: 4520'

COMMENCED: December 7, 1978  
COMPLETED: December 14, 1978

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post rock, shale	0	310	Ran 7 jts. used 8-5/8" surface casing; set and cemented @ 299' with 150 sacks 60-40 pozmix, 50 sacks common, 3% C.C. Cement circulated. Plug down 11:55 p.m., December 7, 1978.
Shale, sand, shale	310	1731	
Anhydrite	1731	1766	
Shale	1766	2405	
Lime and shale	2405	4500	
Lime	4500	4520	
			Ran one drill stem test.
			Ran one electric log.
			Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 720', 20 sacks @ 240', hulls and 10 Sacks @ 40'. Plugging completed 11:15 p.m., December 14, 1978.

STATE OF KANSAS )  
                          )ss  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Charles W. Steincamp  
Charles W. Steincamp

Sworn to and subscribed before me this 21st day of December, 1978.

My commission expires 3-28-80.

Loneita Barry  
Loneita Barry, Notary Public

