


15-135-21041-00-00

FORM CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

WELL PLUGGING RECORD

Ness County, Sec 14 Twp. 17S Rge. (E) 24 (W)
Location as "NE/CNW/SE/SW" or footage from lines C SW NW
Lease Owner Zorger Oil Company
Lease Name Never Well No. 1
Office Address 706 Union Nat'l Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-29 19 75
Application for plugging filed 4-29 19 75
Application for plugging approved 4-29 19 75
Plugging commenced 4-29 19 75
Plugging completed 4-29 19 75
Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4550 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	Surface	278	8-5/8"	270	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid to 720', plug, (50-50 Posmix,) 70 sacks
Fluid to 40, plug, 1/2 sx hulls, 10 sx cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.
Address 701 First National Building
Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF _____, ss.

JAMES L. DONELSON

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

James L. Donelson

701 First Nat'l Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of May 19 75

My commission expires August 25, 1976

Ella Priess

Notary Public

Ella Priess
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Com. Expires Aug. 25, 1976

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
05-02-1975

15-135-21041-00-00

DRILLERS' LOG

ZORGER OIL COMPANY
No. 1 Neyer
C SW NW, Sec. 14-17S-24W
Ness County, Kansas

Elev: 2478 K.B.

Commenced: 4-19-75
Completed: 4-28-75

Surface Casing: 270' of
8-5/8" cemented w/200 sx
common cement, 2% Gel,
3% cc. 4-19-75.

FORMATION

DEPTH

Surface Hole	0 - 278
Shale	278 - 340
Shale & Red Bed	340 - 1142
Blaine Anhydrite	1142 - 1152
Shale & Sand	1152 - 1518
Shale, Sand, Red Bed	1518 - 1776
Anhydrite	1776 - 1809
Shale	1809 - 2370
Lime & Shale	2370 - 4010
Lime	4010 - 4463
Lime & Sand	4463 - 4469
Lime & Chert	4469 - 4479
Lime	4479 - 4550 RTD

05-02-1975

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

DNB DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 1st day of May, 1975.

My Commission Expires:
August 25, 1976

Ella Priess

Ella Priess, Notary Public

Ella Priess
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Comm. Expires Aug. 25, 1976