

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
R.A.R.-82-3-117

NUMBER ¹⁵ 135-24,163-0000

RECEIVED

FEB 14 2002
02-14-0002
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Neyer
WELL NUMBER 1-14
1120 Ft. from S Section Line
4360 Ft. from E Section Line
SEC. 14 TWP. 17s RGE. 24w (X) or (W)

LEASE OPERATOR PELICAN HILL OIL & GAS, INC.
ADDRESS 1401 North ElCamino Real, Suite 207 San Clemente, CA 92672
PHONE/(949) 498-2101 OPERATORS LICENSE NO. 31120

Date Well Completed 10/20/01
Plugging Commenced 6:30AM 10/20/01
Plugging Completed 9:15AM 10/20/01

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)
The plugging proposal was approved on 10/19/01 (date)
by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom _____ T.D. 4620
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put in	Pulled out
		Surface	206	8 5/8	206.85	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each so
1st Plug @ 1830'w/50sks 5th Plug @ 40'w/10sks Circulated 1st Plug 15 Minutes w/51 Vis Mud
2nd Plug @ 1100'w/80sks 10sks In Mouse Hole Plugs displaced with mud
3rd Plug @ 500'w/40sks 15sks In Rat Hole Total 245sks 60/40Poz 6%Gel w/1#FC/sk By Allied
4th Plug @ 230'w/40sks Completed @ 9:15AM 10/20/01

Name of Plugging Contractor Discovery Drilling Co., Inc. License No. 31548
Address P.O. Box 763 Hays, KS 67601


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PELICAN HILL OIL & GAS, INC.
STATE OF CALIFORNIA COUNTY OF ORANGE, ss.

Allen J. Gross, Pres. of Pelican Hill Oil&Gas, Inc. (Employee of Operator) or (Operator)
above described well, being first duly sworn on oath, says: That I have knowledge of the fact
and matters herein contained and the log of the above-described well as filed in
the _____ true and correct, so help me God.

(Signature) Allen J. Gross
(Address) 1401 N. El Camino Real, #207 San Clemente, CA 92672

SUBSCRIBED AND SWORN TO before me this 11 day of February, 2002

My Commission Expires: 11/9/03
Mary J. Miller Notary Public



OR