

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ness County, Sec 14 Twp 17S Rge. (E) 24 (W)

Location as "NE/CNW/SW" or footage from lines C SE SW

Lease Owner IMPERIAL OIL COMPANY

Lease Name Neyer Well No. 1

Office Address 780 Fourth National, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 11 1968

Application for plugging filed November 11 1968

Application for plugging approved November 11 1968

Plugging commenced November 11 1968

Plugging completed November 11 1968

Reason for abandonment of well or producing formation No commercial quantities of oil and/or gas were encountered.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4560 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface casing			277'	3 5/8"	200 sacks	Not pulled.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4560 feet to feet for each plug set.

Set first plug at 900 ft. with 100 sacks cement.
Set second plug at 270 ft. with 20 sacks cement.
Set third plug at 40 ft. with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 18 1968
CONSERVATION DIVISION
Wichita, Kansas

11-18-1968

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil Company

Address 780 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

William A. Sladek (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL COMPANY

(Signature) William A. Sladek

780 Fourth National Bldg., Wichita, Ks.

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 1968

My commission expires March 3, 1970

Mary J. Brown
Mary J. Brown Notary Public.

Rec'd
11-18-1968

Imperial Oil Company
780 Fourth National Bldg.
Wichita, Kansas

Neyer No. 1
C SE SW Sec. 14-17S-24W
Ness County, Kansas

Total Depth: 4560 feet

Elevation: 2481 K.B.

Commenced: 10-31-68

Completed: 11-11-68
Dry Hole

Contractor: Imperial Oil Co., Rig #2

Casing Record: Set 8 5/8" surface casing at 277 feet with 200 sacks of cement.

Figures indicate bottom of formations:

Electric Log Tops:

267' Post rock, sand-shale	Heebner	3865 (-1384)
277' Shale	Toronto	3892 (-1411)
1142' Shale-sand	Lansing	3911 (-1430)
1150' Blaine	Pawnee	4327 (-1846)
1225' Shale	Labette Shale	4408 (-1927)
1500' Dakota Sand	Fort Scott	4415 (-1934)
1670' Shale	Sherokee Shale	4439 (-1958)
1787' Shale-shells	Cherty Conglomerate	4501 (-2020)
1818' Anhydrite	Mississippi Limestone	4518 (-2037)
2505' Shale-lime	Mississippi (Warsaw)	4541 (-2060)
3916' Lime-shale	Total Depth	4561 (-2080)
4033' Lime		
4074' Lime-shale		
4500' Lime-shale		
4560' Dolomite		
4560' Rotary Total Depth		

RECEIVED
STATE CORPORATION COMMISSION
NOV 18 1968
CONSERVATION DIVISION
Wichita, Kansas

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

William A. Sladek
William A. Sladek

Subscribed and sworn to before me this 14th day of November, 1968.

Mary J. Brown
Mary J. Brown, Notary Public

My Commission Expires:
March 3, 1970