

Orig-State Corp. Comm
Copy - Well File
STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERRY BUILDING
WICHITA, KANSAS 67202

Copy - B. A. Conner -9th Floor Price Tower Copy - Mary Crump-OKC

WELL PLUGGING RECORD

Rec'd
01-04-1984

API NUMBER 15-135-22-492-00-00

LEASE NAME Never-BB

TYPE OR PRINT

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

WELL NUMBER 4

SPOT LOCATION 825' ENL & 825' EW

EASE OPERATOR Phillips Petroleum Company

SEC. 15 TWP. 17 RGE. 24 (E) OR (W)

ADDRESS Box 287, Great Bend, Kansas 67530

COUNTY Ness

PHONE #(316) 793-8421 OPERATORS LICENSE NO. 5229

DATE WELL COMPLETED 12-6-83

CHARACTER OF WELL Dry Hole
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMMENCED 12-6-83

PLUGGING COMPLETED 12-6-83

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City, Kansas

IS ALL(-) FILED? Attached IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION Dry Hole DEPTH TO TOP _____ BOTTOM T.D. 4590'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

WELL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Water	0	1055	8 5/8	1045.67	-0-

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. MIRU B.J. Hughes to 4 1/2" drill pipe COOH w/DP & spotted plugs as follows: 30 sx 60-40 Pozmix w/2% gel & 3% CaCl. 4560-4445', 65 sx 1800-1560, 50 sx 1080-898', 20 sx 480-408'. Pushed 8 5/8" plug to 40' & fill w/10 sx cmt to surf. Plug rat hole w/15 sx cmt. Weld plate on csg. Well P&A 12-6-83

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR B. J. Hughes LICENSE No. _____
ADDRESS Great Brnd, Kansas 67530


STATE OF Kansas COUNTY OF Barton, SS.

Kaare A. Westby (EMPLOYEE OF OPERATOR) OR
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND
CORRECT, SO HELP ME GOD.

(SIGNATURE) X Kaare Westby
Kaare A. Westby, Area Manager
(ADDRESS) Box 287, Great Bend, Ks 67530

SUBSCRIBED AND SWORN TO BEFORE ME THIS 3rd DAY OF January, 1984

Velma L. Mog
NOTARY PUBLIC



MY COMMISSION EXPIRES: February 15, 1984