

15-135-22051-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ness SEC. 24 TWP. 17S RGE. 24W E/W
Location as in quarters or footage from lines:
C SE NW

Lease Owner Wolters Drilling Co., Inc.
 Lease Name RUTSCHMANN Well No. 1
 Office Address 420 Hardage Center, 100 S. Main, Wichita, KS
 Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole⁶⁷²⁰²
 Date Well Completed July 5, 1981
 Application for plugging filed July 5, 1981
 Plugging commenced July 5, 1981
 Plugging completed July 5, 1981
 Reason for abandonment of well or producing formation No commercial quantity of oil or gas encountered.
 Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? YES

Locate Well correctly on above Section Platt.

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4600'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @ 920' with 65 sx.
 Set 2nd plug @ 480' with 30 sx.
 Set 3rd plug @ 40' with 10 sx.

Job complete @ 2:00 a.m., 7/05/81.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.



STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, KS
 (Address) 67202

SUBSCRIBED AND SWORN TO before me this 7th day of July

Suzanne M. Hofer
 Suzanne M. Hofer Notary Public.

My Commission Expires: 2-4-85



15-135-22051-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	Wolters Drilling Co., Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	RUTSCHMANN #1
LOCATION:	C SE NW, Section 24-17S-24W Ness County, Kansas
SPUD DATE:	6/26/81
COMPLETION DATE:	7/05/81

0	460	Shale & Sand
460	1030	Shale
1030	1700	Shale & Sand
1700	1778	Sand & Shale
1778	1812	Anhydrite
1812	2041	Sand & Shale
2041	3810	Shale
3810	3950	Shale & Lime
3950	4151	Lime & Shale
4151	4223	Shale & Lime
4223	4312	Lime & Shale
4312	4405	Lime
4405	4430	Lime & Shale
4430	4455	Lime
4455	4507	Lime & Shale
4507	4600	Lime, Sand & Shale
	4600	Rotary Total Depth

Spud hole @ 5:30 p.m., 6/26/81. Drilled 459' of a 12 1/4" hold. Ran 10 jts. of 8 5/8" casing set @ 456' K.B. with 255 sx. common 2% gel, 3% c.c. Pumped plug to 441' K.B. Plug was down @ 12:45 a.m., 6/27/81. Cement did circulate.

TD @ 4600'. Set 1st plug @ 920' with 65 sx. Set 2nd plug @ 480' with 30 sx. Set 3rd plug @ 40' with 10 sx. Plug was down @ 2:00 a.m., 7/05/81.

SAMPLE TOPS:

Anhydrite 1778'
B/Anhydrite 1812'

STATE OF KANSAS)
)
COUNTY OF SEDGWICK)

07-10-1981
RECEIVED
STATE CORPORATION COMMISSION
10/1981
CONSERVATION DIVISION
Kansas

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the RUTSCHMANN #1, C SE NW, Section 24-17S-24W, Ness County, Kansas.

ABERCROMBIE DRILLING, INC.
BY: Jack L. Partridge
Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 7th day of July, 1981.

Suzanne M. Hofer
Suzanne Hofer, Notary Public

