

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-135-21518-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

County. Sec. 23 Twp. 17S Rge. 24W E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
NW NW SW


Lease Owner Reed Oil Company  
Lease Name Anspaugh Well No. #1  
Office Address Box 2, Chanute, Kansas 66720  
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date Well completed October 9, 1978 19  
Application for plugging filed October 9, 1978 19  
Application for plugging approved October 9, 1978 19  
Plugging commenced October 9, 1978 19  
Plugging completed October 9, 1978 19  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 4520'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set. Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 600', 20 sacks @ 300', hulls and 10 sacks @ 40', 2 sacks each in rathole and mousehole. Plugging completed at 2:00 p.m., October 9, 1978.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company

STATE OF KANSAS COUNTY OF BARTON, ss.  
Kenneth J. Link (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link President  
P. O. Box 355, Great Bend, Kansas 67530  
(Address)


SUBSCRIBED AND SWORN TO before me this 13th day of October, 1978.

Loneita Barry  
Loneita Barry Notary Public.

My commission expires 3-28-80.

RECEIVED  
STATE CORPORATION COMMISSION

NOV - 3 1978  
11-03-1978  
CONSERVATION DIVISION  
Wichita, Kansas



15-135-21518-00-00

D R I L L E R S    L O G

#1 Anspaugh

CASING RECORD:  
9 jts. new 20#  
8-5/8" surface  
casing

COMPANY: Reed Oil Company  
CONTRACTOR: Strata Drilling Company

DESCRIPTION: NW NW SW  
Section 23-17S-24W  
Ness County, Kansas

COMMENCED: October 3, 1978

ELEVATION: 2489' KB

TOTAL ROTARY  
DEPTH: 4520'

COMPLETED: October 9, 1978

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil, sand	0	375	Ran 365' new 20# 8-5/8" surface casing; set and cemented at 370' with 225 sacks common cement, 2% gel, 3% C.C. Cement circulated. Plug down at 11:30 p.m., October 3, 1978.
Shale, sand, shale	375	1794	
Anhydrite	1794	1828	
Shale	1828	2450	Ran no electric logs or drill stem tests.
Lime and shale	2450	3850	
Lime	3850	4050	Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 600', 20 sacks @ 300', hulls and 10 sacks @ 40', 2 sacks each in rathole and mousehole. Plugging completed at 2:00 p.m., October 9, 1978.
Lime and shale	4050	4345	
Lime	4345	4425	
Lime and shale	4425	4510	
Lime	4510	4520	

STATE OF KANSAS )  
                          )ss  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

*Kenneth J. Link*  
Kenneth J. Link, President

Sworn to and subscribed before me this 13th day of October, 1978.

My commission expires 3-28-80.

*Loneita Barry*  
Loneita Barry, Notary Public

