

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-22,571-00-00

LEASE NAME Habiger-Keilman

WELL NUMBER #5

4950 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 21 TWP. 17 RGE. 24 (E) or (W)

COUNTY Ness

Date Well Completed _____

Plugging Commenced 10-4-88

Plugging Completed 10-21-88

LEASE OPERATOR Palomino Petroleum

ADDRESS Route #5-Box 51-C, Newton, Kansas 67114

PHONE # (316) 283-0232 OPERATORS LICENSE NO. 5161

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 20, 1988 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4380'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	308'	None
				5-1/2"	4369'	1,052.20'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Dumped sand to 4200' and 5 sacks cement. Shot casing at 3200', 2500', 1600' & 1050'. Pulled 34 joints of 5-1/2" casing. Allied plugged well with 300# hulls, 50 sacks 60/40 pozmix cement. with 6% gel, 10 sacks gel, 100# hulls, released plug and pumped 150 sacks cement. Max pressure 800 psi and shutin 500 psi.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 24th day of October, 1988

Irma M. Leatherman
Notary Public

My Commission Expires:

