

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-135-21,574-00-00

LEASE NAME Keilman "C"

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER #1

4620 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 21 TWP. 17 RGE. 24 (E) or (W)

COUNTY Ness

Date Well Completed \_\_\_\_\_

Plugging Commenced 6-23-87

Plugging Completed 7-2-87

LEASE OPERATOR Palomino Petroleum

ADDRESS Route 5, Box 51C-Newton, Kansas 67114

PHONE (316)-283-0232 OPERATORS LICENSE NO. 5161

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4392'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	281'	None
				5-1/2"	4375'	1,464.19'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 4220' and 5 sacks cement. Shot casing at 3500', 2500', 2000', 1800', 1400'. Pulled 40 joints of 5-1/2" casing. Allied squeezed well with 3 sacks hulls, 10 sack gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 150 sack 60/40 pozmix cement with 6% added gel. Ma. pressure was 700 psi and shutin 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED  
 JUL 8 1987  
 07-08-1987  
 STATE CORPORATION COMMISSION  
 WICHITA, KANSAS  
 Signature) James W. Rockhold  
 (Address) Box 698, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 3rd day of July, 1987

Iona M. Leatherman  
 Notary Public

My Commission Expires:

