

15-135-21700-00-00

D R I L L E R S L O G

#3 Rupp

CASING RECORD: 8 jts. new 20# 8-5/8" surface casing	COMPANY: John Jay Darrah, Jr.	DESCRIPTION: SW NW SW Section 21-17S-24W Ness County, Kansas
TOTAL ROTARY DEPTH: 4380'	CONTRACTOR: Strata Drilling Company	COMMENCED: October 27, 1979
	COMPLETED: November 2, 1979	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post rock, shale	0	340	Ran 326' new 20# 8-5/8" surface casing; set and cemented @ 332' with 200 sacks common cement, 2% gel, 3% C.C. Cement circulated. Plug down at 10:00 p.m., October 27, 1979.
Shale, sand, shale	340	1671	
Anhydrite	1671	1703	
Shale	1703	2544	
Lime	2544	2790	
Lime and shale	2790	4070	
Lime	4070	4210	
Lime and shale	4210	4380	Ran 5 1/2" casing, set @ 4376 1/2' with 100 sacks Halco Lite, 125 sacks 60-40 pozmix, 12% salt. Plug down at 10:45 a.m., November 2, 1979.

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1981
08-24-1981
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Charles W. Steincamp
Charles W. Steincamp

Sworn to and subscribed before me this 5th day of November, 1979.

My appointment expires 3-28-80.

Loneita Barry
Loneita Barry, Notary Public

