

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado De by Bldg
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-135-23885-0080
API NUMBER 15-135-23585-00-00

KANSAS CORPORATION COMMISSION
12-21-1995
DEC 21 1995
CONSERVATION DIVISION
WICHITA, KS

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

*AMB
KCC*

LEASE NAME Otis

WELL NUMBER 1-16 1-6

_____ Ft. from S Section Line

_____ Ft. from E Section Line

SEC. 6 TWP. 17 SRGE. 24 (SEMM(W))

COUNTY Ness

Date Well Completed _____

Plugging Commenced 12-7-95

Plugging Completed 12-11-95

LEASE OPERATOR Coyote, Inc.

ADDRESS 217 S. Broadway Wichita, Ks. 67202

PHONE# 316 263-1200 OPERATORS LICENSE NO. 31565

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4565'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	206.6	none
				4 1/2"	4561'	2416'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Plugged off bottom with sand to 4450' and 4 sacks cement. Shot pipe at 2408'. Pulled up to 1760', pumped 50 sacks cement (60/40 6% gel) displaced with 9 sacks gel. Pulled to 1000', pumped 80 sacks cement, displaced with gel. Pulled to 500', pumped 40 sacks cement, pulled to 230' pumped 40 sacks cement, pulled rest of casing, topped off with 10 sacks cement. (60/40 6% gel) Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Coyote, Inc. Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 20th day of December, 19 95

Irene Herzberg
Notary Public

My Commission Expires:
USE ONLY ONE SIDE OF EACH FORM

