

STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

Re: Re: 02-3-111

API NUMBER 15-135-20,925-0000

LEASE NAME Vermillion "MA"

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

3300 Ft. from S Section Line

600 Ft. from E Section Line

SEC. 6 TWP. 17 RGE. 24 (N or W)

COUNTY Ness

Date Well Completed Nov. 1974

Plugging Commenced 4-22-93

Plugging Completed 4-22-93

LEASE OPERATOR Petroleum, Inc.

ADDRESS 301 North Main, Suite 900

PHONE#(316) 291-8200 OPERATORS LICENSE NO. 5238

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 22, 1993 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Submitted with Form CP-1

Producing Formation Miss Depth to Top 4482' Bottom 4488' T.D. 4498'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	262	None
				5 1/2"	4497	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set C.I.B.P. @ 4300', perf. 5 1/2" csg. at 1150' w/4 shots. Pumped 170sx 60/40 poz, 6% gel and 100# hulls down 5 1/2" csg. MP. 700#, pumped 20sx. 60/40 poz., 6% gel down annulus M.P. 600#

Name of Plugging Contractor Allied Cementing Co. License No. \_\_\_\_\_

Address P.O. Box 420 Ness City, Kansas 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.

Paul Kreutzer (Employee of Operator) or (Operator) c

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Paul Kreutzer

(Address) 301 North Main, Suite 900  
Wichita, KS 67207



AND SWORN TO before me this 4th day of May, 19 93

Sherry Fraser  
Notary Public  
RECEIVED  
STATE CORPORATION COMMISSION  
05-05-1993  
MAY - 5 1993  
Form CP-4  
Revised 05-88

My Commission Expires: 3-20-94

USE ONLY ONE SIDE OF EACH FORM

CONSERVATION DIVISION  
Wichita, Kansas