

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER S135-24043-0000

LEASE NAME Potter "C"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
2310 Ft. from S Section LI
2970 Ft. from E Section LI

LEASE OPERATOR JOHN O. FARMER, INC.

SEC. 6 TWP. 17s RGE. 24w COR. ()
COUNTY Ness

ADDRESS P.O. Box 352 Russell, Kansas 67665

PHONE# (785) 483-3144 OPERATORS LICENSE NO. 5135

Date Well Completed 12/23/97

Character of Well D&A

Plugging Commenced 9:15AM 12/23/97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12:00PM 12/23/97

The plugging proposal was approved on 12/22/97 (date)

by Scott Alberg (KCC District Agent's Name)

Is ACU-1 filed? Yes If not, is well log attached? No Log

Producing Formation None Depth to Top _____ Bottom _____ T.O. 4505

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	201	8 5/8	201.25	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from feet to feet each

1st Plug @ 1850' w/50sks 10 sks in Mouse Hole Circulated 1st Plug 15 Minutes with 49 Vis Mud

2nd Plug @ 1110' w/80sks 15sks In Rat Hole Plugs Displaced with mud

3rd Plug @ 650' w/40sks 235sks 60/40Poz 6%Gel w/1#ES/sk By Allied

4th Plug @ 240' w/40sks Completed @ 12:00PM 12/23/97

Name of Plugging Contractor Discovery Drilling, Inc. License No. 31548

Address P.O. Box 763 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF Kansas COUNTY OF Russell, ss.


John O. Farmer III (Operator of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated; and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) John O. Farmer III
(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 21st day of January, 19 98

Margaret A. Schulte
Notary Public
Margaret A. Schulte

USE ONLY ONE SIDE OF EACH FORM



01-23-1998 Form (Revised 02)