

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Wichita State Office Building  
130 South Market, Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-177

API NUMBER 15-051-24,424 0000

LEASE NAME Harold

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

4950 Ft. from S Section Line

660 Ft. from E Section Line

LEASE OPERATOR R.P. Nixon Operations, Inc.

SEC. 10 TWP. 13S RGE. 16W (E) or (W)

ADDRESS 207 West 12th Street Hays, KS 67601

COUNTY Ellis

PHONE #(913) 628-3834 OPERATORS LICENSE NO. 5252

Date Well Completed 8/19/86

Character of Well oil

Plugging Commenced 2/10/97

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

Plugging Completed 2/10/97

The plugging proposal was approved on 2/10/97 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 Filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation L/KC, Arbuckle Depth to Top 3202' (L/KC) Bottom 3437' (BKG) TD 3500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled
				8 1/2"	210'	None
				5 1/2"	3498'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Tied onto 5 1/2" pumped 50 sx 60/40 Poz w/10% gel and 250# of hulls. Then pumped 15 sx gel w/100# of hulls. Then pumped 130 sx 60/40 Poz, 10% gel w/150# of hulls. Had 500# pressure while mixing w/400# shut in pressure. Cement was visible between 8 1/2" and 5 1/2" casing. Job complete @ 12:00 p.m. Witnessed by Marvin Miller, PART II.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jay-Lan Corporation License No. 5128

Address 207 West 12th Street Hays, KS 67601-3898

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Dan A. Nixon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 207 West 12th St. Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 11th day of February, 1997



[Signature]  
Notary Public

My Commission Expires: 5-24-97