



15-135-20185-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1968
CONSERVATION DIVISION
Wichita, Kansas
09-23-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Burton of Pickrell Drlg. has this
date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg. Wichita, Ks.

Lease Name: Hall "J" Well No. 1

Location: SW SE Sec. 2 Twp. 17 Rge. 24 (E)(W) X

County: Ness Total Depth 4500' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Burton was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 900' and displace
70 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Geo F. Massey
Conservation Division Agent