



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. - 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUL 8 1968

CONSERVATION DIVISION
 Wichita, Kansas

07-08-1968

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Burton of Pickrell Drlg. has this

date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 Fourth Nat'l Bldg., Wichita, Ks.

Lease Name: ~~Harrison~~ # 0117 (OWWO) Well No. 1

Location: SW SW NE Sec. 2 Twp. 17 Rge. 24 (E)(W) X

County: Ness Total Depth 4595 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

Gun bits, circulate heavy mud, set cementing plug at 900' and displace

70 sc cement thru drill pipe. Heavy mud to 180' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole

with 2 sc cement.

Very truly yours,

Geo F. Massey
 Conservation Division Agent