

State of Kansas



15-135-20851-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 P. O. Box 17027 3830 S. Meridian
 WICHITA, KANSAS 67217

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

FEB 27 1974

CONSERVATION DIVISION
 (Wichita, Kansas)

02-27-1974

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. French of Pickroll Drlg. has this

date requested permission to plug the following described well:

Mr. French guarantees payment of the plugging fee.

Operator's full Name: Pickroll Drlg. Co. & Petro. Chem.

Complete Address: 705 4th Nat'l Bk. Bldg., Wichita, Ks.

Lease Name: Herchem "I" Well No. 1

Location: C NW NW Sec. 1 Twp. 17 Rge. (E)(W) 24

County: Ness Total Depth 4508' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. French was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 750' and displace

70 sk cmt thru drill pipe. Heavy mud to 215' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. E. Massey
 Conservation Division Agent