

State of Kansas



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN - 8 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Williamson of Vaughan Drlg. Co. has this date requested permission to plug the following described well:

Mr. Williamson guarantees payment of the plugging fee.

Operator's full Name: Mull Drlg Co., Inc.

Complete Address: 1625 Wichita Plaza Wichita, Ks.

Lease Name: Doebbling Well No. 2

Location: C SW NE Sec. 32 Twp. 18 Rge. 24 (E)(W) X

County: Ness Total Depth 4441 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Williamson was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 1330' and displace
100 sc cement thru drill pipe. Heavy mud to 420' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Geo. F. Massie
Conservation Division Agent