

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAYES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Pfannensteil of Leben Drlg. has this

date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: McClure & Tilco

Complete Address: 815 Wichita Plaza Wichita, Kansas

Lease Name: Miner "A" Well No. I

Location: C SW SW Sec. 31 Twp. 18 Rge. 24 (E)(W) X

County: Ness Total Depth 4460 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace
70 sc cement thru drill pipe. Heavy mud to 390' set cementing plug and displace
20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc
hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

Geo. J. Messey
Conservation Division Agent