



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Delaney of Leben Drlg. has this

date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Leben, Et al

Complete Address: 200 W. Douglas Wichita, Kansas

Lease Name: Margheim Well No. 1

Location: SE NW SW Sec. 30 Twp. 18 Rge. (E)(W) 24

County: Ness Total Depth 4490 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Delaney was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace
50 sk cmt thru drill pipe. Heavy mud to 400' set cementing plug and
displace 25 sk cmt. Heavy mud to 40' set cementing plug, 1/2 sk hulls
and 10 sk cmt to base of cellar.

Very truly yours,

Conservation Division Agent