



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 19 1974
08-19-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Norwood of DNB' Drlg. has this

date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Thomas E. Black, Black Petroleum Co.

Complete Address: 545 O. W. Garvey Bldg., Wichita, Ks.

Lease Name: J. Kraus Well No. 1

Location: CNE NE Sec. 21 Twp. 17 Rge. (E)(W) 24

County: Ness Total Depth 4445' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Norwood was instructed to plug the well as follows:

Gun pits, circulate heavy mud, displace 70 sk cmt at 720' thru drill pipe.

Heavy mud to 240' and displace 20 sk cmt thru drill pipe. Heavy mud to

40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey
Conservation Division Agent