



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Crowe of Garvey Drlg. has this

date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 200 W. Douglas Wichita, Ks.

Lease Name: O'Brien "B" Well No. 3

Location: SW NW SW Sec. 9 Twp. 11 Rge. (E)(W) 18

County: Ellis Total Depth 3218 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Crowe was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace

70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Sam F. Murrain
Conservation Division Agent