



15-135-20709-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1973
CONSERVATION DIVISION
Wichita, Kansas
02-09-1973

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Rodie of R & W Drlg. has this

date requested permission to plug the following described well:

Mr. Rodie guarantees payment of the plugging fee.

Operator's full Name: Beardmore Oil, Inc.

Complete Address: 700 One Twenty Bldg., Wichita, Ks.

Lease Name: Rufenacht Well No. 1

Location: NE SE Sec. 27 Twp. 17 Rge. (E)(W) 24

County: Ness Total Depth 4456' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Rodie was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 700' and displace

70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey
Conservation Division Agent