



15-135-20632-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1972
CONSERVATION DIVISION
Wichita, Kansas
06-27-1972

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Art Hunt of Rains-Williamson Oil Co. Inc., has this date requested permission to plug the following described well:

Mr. Hunt guarantees payment of the plugging fee.

Operator's full Name: Beardmore Oil, Incorporated,

Complete Address: 700 One-Twenty Building, Wichita, Kansas.

Lease Name: Rufenacht Well No. A-1

Location: NE-NW Sec. 27 Twp. 17 Rge. (E)(W) 24

County: Ness Total Depth 4495' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hunt was instructed to plug the well as follows:

257'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 475'.

Circulate hole with heavy mud. Pull DP to 700' and displace 110 Cu. Ft. cement thru DP. Pull DP to 280' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Pichole
Conservation Division Agent