



15-135-20550-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 8 1972  
CONSERVATION DIVISION  
LEADERS REGS

02-08-1972

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Moore of C & G Drlg. has this

date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Dane G. Hansen, Trust

Complete Address: Box 187 Logan, Kansas

Lease Name: Paul "A" Well No. 1

Location: NW SE Sec. 26 Twp. 17 Rge. (E)(W) 24

County: Ness Total Depth 4497' Oil Well       

Gas Well        Input Well        SWD Well        D & A XX Lost Hole       

Mr. Moore was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace

70 sk cmt thru drill pipe. Heavy mud to 300' set cementing plug and ~~XXX~~

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo F. Manning  
Conservation Division Agent