



15-135-21111-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

NOV 3 1975
11-03-1975
CONSERVATION DIVISION
WICHITA, KANSAS

Dear Sir:

Mr. Norwood of DNB Drlg. has this

date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Walters Drlg. Co.

Complete Address: 400 Insurance Bldg., Wichita, Ks.

Lease Name: A.P.H. Well No. 1

Location: C NE NE Sec. 14 Twp. 17 Rge. (E)(W) 24

County: Ness Total Depth 4515' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Norwood was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 720' thru drill

pipe. Heavy mud to 250' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent