



15-135-2134-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED

APR 18 1977
04-18-1977

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Conway of Slawson Drlg. has this

date requested permission to plug the following described well:

Mr. Conway guarantees payment of the plugging fee.

Operator's full Name: Walters Drlg. Co.

Complete Address: 400 Insurance Bldg., Wichita, Ks.

Lease Name: Lynch "B" Well No. 1

Location: C NW SE Sec. 13 Twp. 17 Rge. (E)(W) 24

County: Ness Total Depth 4470' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Conway was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 720' thru drill

pipe. Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent