



15-135-20090-00-00

ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

DEC 1 1967  
12-11-1967

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Pfannenstiel of Leben Drlg. Inc. has this

date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Tilco, EtAl

Complete Address: 815 Wichita Plaza Wichita, Kansas

Lease Name: Rufenacht Well No. 1

Location: C NE SW Sec. 9 Twp. 17 Rge. 24 (E)(W) X

County: Ness Total Depth 4425 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Pfannenstiel was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 900' and displace  
100 sc cement thru drill pipe. Heavy mud to 270' set cementing plug and  
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Paul J. Mancy  
Conservation Division Agent