

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5822
Name: Val Energy, Inc.
Address 1: 200 West Douglas
Address 2: Suite 520
City: Wichita State: KS Zip: 67202 +
Contact Person: Todd Allan
Phone: ()
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: SWD Permit #:
 ENHR Permit #: Gas Storage Permit #:
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Depth to Top: Bottom: T.D.
Depth to Top: Bottom: T.D.
Depth to Top: Bottom: T.D.

API No. 15 - 15.159.22635.00.00
Spot Description: NE SW NW NE Sec. 12 Twp. 21 S. R. 6 East West
696 4728 Feet from North South Line of Section
2275 2263 Feet from East West Line of Section
GPS-KCC
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Rice
Lease Name: Krehbiet Trust Well #: 1-12
Date Well Completed:
The plugging proposal was approved on: (Date)
by: Virgil Clothier (KCC District Agent's Name)
Plugging Commenced: 4/27/12
Plugging Completed: 4/30/12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			13.375	80'	
			8 5/8"	350'	None
			5 1/2"	3444	2600'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran bailer down, TD @ 3478', dumped sand. Ran bailer down, sand @ 3302'. Dumped 5sx cement. Got stretch of 22". Cut casing loose @ 2600'. Pulled up to 781'. Mixed 35sx @ 750'. Circulated 180sx @ 450'. Pulled pipe out. Plugging complete.

Plugging Contractor License #: 31529 Name: Mike's Testing and Salvage, Inc.
Address 1: PO Box 467 Address 2:
City: Chase State: KS Zip: 67524 +
Phone: (620) 938-2943
Name of Party Responsible for Plugging Fees: Val Energy, Inc.
State of Kansas County, Rice, ss.
Mike Kelso Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mike Kelso

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAY 30 2012
KCC WICHITA