


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-051-30633-0000  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Ellis County, Sec. 26 Twp. 13 Rge. 20 (E) W (W)  
Location as "NE/CNW&SW&" or footage from lines SE 1/4 NW NE ANB 111  
Lease Owner Burch Drilling Co., Inc.  
Lease Name Herman #2 Well No. \_\_\_\_\_  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 12-4-59 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 12-7-59 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3810 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	225'	none
				4-1/2"	3804'	3206'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 3810' and found it open.  
Pushed plug to 3460' and ran sand on top of plug to 3455'. Pulled 4 1/2" casing to 600', and circulated pipe with 26 sacks of gel mud. Pumped in 20 sacks of cement at 600'. Pulled pipe to 200' and pumped in 20 more sacks of cement. Pulled rest of casing, cleared hole and bailed mud to 30', ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING COMPLETED

JAN 8 1960

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Co.  
Address Chase, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.  
I, Noel J. Knight (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of December, 1959

My commission expires 9-27-62

Thomas V. Suggs  
Notary Public.

1505/30633 0000  
WELL LOG

Burch Drilling Co., Inc.  
# 2 NEKMAN  
SE NW NE  
Ellis County, Kansas

8 5/8" set @ 225 w/150 ex.  
ELEVATION: 2163'  
COMM: 12-9-58  
CORN: 12-18-58  
4 1/2" set @ 3804' w/125 ex.

310 Shale  
1471 Shale & Shells  
1517 ANHYDRITE Anhydrite  
2225 Shale & Lime streaks  
2456 Lime & Shale  
3780 Lime  
3810 Cherty Lime  
  
3810 Total Depth

TOPS

Neabner 3410  
Toronto 3431  
Lansing 3440  
Base Kansas City 3702  
Marmaton 3748  
Arbuckle 3803

DET # 1 3443-3456 Open 1 hr.  
Rec. 630' gas plus 45' oil plug  
45' HOCH. INHP (30min) 12400  
IFF & FFF 04, FBHP (30 min) 12500

DET # 2 3580-3600 Open 2 hr.  
Rec. 310' gas plus 85' oil plug  
INHP (30min) missed, IFF 0,  
FFF 0, FBHP (30min) 11200

DET # 4, 3, 5 Tool plugged.

REGISTRATION DIVISION  
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDWICK:

I, Karl M. Burch, President of Burch Drilling Co., Inc. being duly sworn on oath, state: That I have knowledge of the facts, statements, and matters herein contained and that the same are true and correct.

Karl M. Burch

Subscribed and sworn to before me this 16th day of January, 1959.

Pinny Larrison  
Notary Public

By commission expires: July 27, 1960.