

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33874
Name: Custer Oil & Gas, LLC
Address 1: Post Office Box 628
Address 2: _____
City: Barnsdall State: OK Zip: 74002 + _____
Contact Person: Norma Standridge
Phone: (918) 847-2531
Type of Well: (Check one) ☒ Oil Well ☐ Gas Well ☐ OG ☐ D&A ☐ Cathodic
☐ Water Supply Well ☐ Other: _____ ☐ SWD Permit #: _____
☐ ENHR Permit #: _____ ☐ Gas Storage Permit #: _____
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 019-19903-00-00
Spot Description: NESENWSE
NE - SE - NW - SE Sec. 1 Twp. 35 S. R. 11 ☒ East ☐ West
1,970 Feet from ☐ North / ☒ South Line of Section
1,361 Feet from ☒ East / ☐ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
☐ NE ☐ NW ☒ SE ☐ SW
County: Chautauqua
Lease Name: Carrie Crane Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: Duane Sims (KCC District Agent's Name)
Plugging Commenced: 3/25/2008
Plugging Completed: 3/25/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		no casing info on this well			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

50' plug at TD, 50' plug at 650' and 350' to surface....Ran 1" to 1100' and spotted 25 sack plug. Pull 1" out and pulled 2" casing. Casing pulled into at 300'. Ran 1" down 8 5/8" casing to 650' and spotted 20 sack plug. Pulled 1" out and perforated casing at 350'. Ran 1" back into 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 155 sacks of cement were used to plug this well. Casing was cut off and location restored

Plugging Contractor License #: 32884 Name: Elmore's, Inc.
Address 1: P. O. Box 87 Address 2: _____
City: Sedan State: KS Zip: 67361 + _____
Phone: (620) 725-5538
Name of Party Responsible for Plugging Fees: Custer Oil & Gas, LLC
State of Oklahoma County, Osage, ss.
Norma Standridge ☒ Employee of Operator or ☐ Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Norma Standridge

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
JUN 06 2012
KCC WICHITA

STATEMENT

7757

ELMORE'S INC.

Box 87 - 776 HWY99

Sedan, KS 67361

Cell: (620) 249-2519

Eve: (620) 725-5538

Date

3-25-08

Customer Custer Oil & Gas -1

Address _____

City _____ State _____ Zip _____

Qty.	Description	Price	Amount
10	hr Pulling Unit	105.00	1050.00
5	hr Cement Pump	80.00	400.00
5	hr Water Truck	70.00	350.00
1	Bowlk Tank	60.00	60.00
1	Perforation At 350'	200.00	200.00
1100'	1" Tubing	.10	110.00
155	SKS Cement	7.75	1201.25
			3371.25
	Plug Job (Carrie Crane)	Tax	212.39
	Ram 1" IN 2" To 1100'	\$	3583.64
	Spotted 25 SKS Cement		
	Pulled 1" Out Pulled Tubing Into		
	AT 200' Ram 1" Down 8 5/8 Casing		
	To 650' Spotted 20 SKS Cement Pulled		
	1" Out 1 Perforated 8 5/8 At 350' Ram		
	1" To 350 Cemented To Surface Inside		
	+ Out Side Casing With 110 SKS.		

Thank You -- We appreciate your business!

Rec'd. by _____

TERMS: Account due upon receipt of services. A 1 1/2% Service Charge, which is an annual percentage rate of 18% will be charged to accounts after 30 days.

RECEIVED
JUN 06 2012
KCC WICHITA