

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31819
Name: Cholla Production, LLC
Address 1: 7851 S. Elati Street ; Suite 201
Address 2: _____
City: Littleton State: CO Zip: 80120 + 8081
Contact Person: Emily Hundley-Goff
Phone: (303) 623-4565
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Morrow Depth to Top: 4652 Bottom: 4686 T.D. 4765
Atoka Depth to Top: 4550 Bottom: 4560 T.D. _____
Marmaton Depth to Top: 4350 Bottom: 4354' T.D. _____

API No. 15 - 171-20825-00-00
Spot Description: _____
- - SE SE Sec. 32 Twp. 19 S. R. 33 East West
660 Feet from North / South Line of Section
660 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Scott
Lease Name: Bontrager Well #: 1-32
Date Well Completed: _____
The plugging proposal was approved on: 5/29/12 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Plugging Commenced: 5/29/12
Plugging Completed: 5/31/12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	262'	NONE
		Production	4 1/2"	4765'	1220'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP # 1 @ 4506' , set CIBP # 2 @ 4304' & cap w/ 2 sks cement . Cut Csg @ 2223' , NOT FREE , squeeze down 4 1/2" casing w/ 50 sks Class "C" cement & displace w/ mud to 2000' . Cut & pull 4 1/2" casing from 1220' . Run tbg @ 1200' , Mix & spot 80 sks Class "C" cement up to 905' . Pull up hole w/ tbg @ 290' , mix & pump 120 sks Class "C" cement & circulate to surface . POH w/ tbg & leave full .

RECEIVED

Plugging Contractor License #: 33338 JUN 07 2012 Name: Orr Enterprises, Inc.
Address 1: P.O. Box 1706 KCC WICHITA Address 2: _____
City: Duncan State: Oklahoma Zip: 73534 + 1706
Phone: (580) 467-0258

Name of Party Responsible for Plugging Fees: Cholla Production, LLC
State of Colorado County, Arapahoe , ss.
Emily M. Hundley-Goff Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Emily M. Hundley-Goff

AP