

15735-20212-0000 R

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ness County. Sec. 4 Twp. 17S Rge. (E)23 (W)

Location as "NE/CNWxSWx" or footage from lines C SW NW

Lease Owner Mull Drilling Company, Inc.

Lease Name HARKNESS Well No. 1

Office Address 1625 Wichita Plaza - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-5 19 68

Application for plugging filed 12-5 19 68

Application for plugging approved 12-5 19 68


Plugging commenced 12-5 19 68

Plugging completed 12-5 19 68

Reason for abandonment of well or producing formation No oil or gas found
in commercial quantities.

If a producing well is abandoned, date of last production -- 19 --

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas 4470'

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4479 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	246	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted 100 sacks cement at 720'. Spotted 20 sacks same at 240'. Set solid bridge at 40' and cemented with 10 sacks. Completed at 6:30 AM 12-5-68.

RECEIVED
STATE CORPORATION COMMISSION
12-23-68
DEC 23 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.
Address 1425 Wichita Plaza - Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains
1425 Wichita Plaza - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of December, 19 68

My commission expires 6-30-71 Sherry Gish Notary Public.

ROTARY DRILLING LOG

Operator: Mull Drilling Company, Inc.
 HARKNESS #1
 C SW NW 4-17S-23W
 Ness County, Kansas

Contractor: Rains & Williamson
 Oil Co., Inc.
 Commenced: 11-22-68
 Completed: 12-5-68
 Casing: 8-5/8" @ 246/160 sx.

Formations

Rock and Shale	162'
Blue Shale	243'
Shale	666'
Shale and Sand	825'
Shale and Shells	1185'
Sand	1408'
Shale	1469'
Red Bed and Shale	1745'
Anhydrite	1785'
Shale and Shells	1865'
Shale	2107'
Shale, Shells & Lime	2390'
Shale and Lime	2772'
Lime and Shale	2860'
Shale and Lime	2965'
Shale and Chalky Lime	3125'
Shale and Lime	3820'
Lime	4268'
Lime and Shale	4350'
Shale and Cherty Lime	4413'
Lime and Chert	4432'
Lime	4436'
Lime and Shale	4445'
Lime	4449'
Lime and Chert	4459'
Lime and Shale	4479'
Rotary Total Depth (D & A)	4479'
	4470'

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 23 1968
 CONSERVATION DIVISION
 Wichita, Kansas


We certify the above log is true
 and correct to the best of our
 knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.



 Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the
 State of Kansas, County of Sedgwick, this 11th day of December, 1968.



 Sherry Gish Notary Public

My Commission Expires:
 June 30, 1971