

R

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -135 -21,174 -00-00 (of this well)

Operator's Full Name Abercrombie Drilling, Inc.

Complete Address 801 Union Center, Wichita, Kansas

Lease Name Phelps Well No. 1

Location 110° E of C: W/2 W/2 NW Sec. 9 Twp. 17 Rge. (E) (W) 24

County Ness Total Depth 4460'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 5 A Day 15 Month 4 Year 1976

The above well was plugged as follows:

RTD 4460' 8 5/8 csg set 262' cwc 200 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 700' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED  
04-19-1976  
CONSERVATION DIVISION  
WICHITA, KANSAS

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Messing  
Well Plugging Supervisor

DATE 4-20-76

INV. NO. 3080-W