

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

REC'D  
07-16-1981

200 Colorado Derby Bldg.  
Wichita, KS 67202

API Number 15- 132-22, 064-00-00

Operator's Full Name WALTERS DRILLING COMPANY, INC.

Complete Address 420 HARDAGE CENTER, WICHITA, MO.

Lease Name PHELPS Well No. # 1-C"

Location 1/40' - SE - C - SW - NW Sec. 9 Twp. 17 Rge. 24 (East) (West)

County NESS Total Depth 4460 EF

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor SLAWSON DRILLING COMPANY, INC

200 DOUGLAS BLDG.

Address BROADWAY + DOUGLAS, WICHITA, MO. License No. \_\_\_\_\_

Operation Completed: Hour: 1:30 AM Day: 15 Month: JULY Year: 19 81

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

8 5/8" - 368' EF SQ CUM w/275' Formix 60/40 @ 2% GEL - 3% CA-CL.

ORDERED 110' ST 50/50 Formix 4% GEL - 3% CA-CL. TO 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1' ST Plug. @ 900' EF w/65' ST CMT.

2' ND Plug. @ 390' EF w/30' ST CMT.

3' RD Plug. @ 40' EF w/10' ST CMT. SOLID BRIDGE HALL'S - PLUG.

5' ST IN RAT HOLE

CEMENTED BY WALLBURTON CMT.

I hereby certify that the above well was plugged as herein stated.

INVESTIGATED

Signed: Marvin Schmidt  
Conservation Division Agent

DATE 8-26-81

INV. NO. 6337-W