

15-135-20090-00-00

Form CP-3  
Rev. 6-26-62

 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

DEC 11 1967  
12-11-1967

Operator's Full Name Tilco, Etal  
Complete Address: 815 Wichita Plaza Wichita, Kansas  
Lease Name Rufenacht Well No. 1  
Location C NE SW Sec. 9 Twp. 17 Rge. 24 (E)    (W) X  
County Ness Total Depth 4425  
Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A X  
Other well as hereafter indicated:     
Plugging Contractor: Leben Drilling, Inc.  
Address: Wichita, Kansas License No.     
Operation Completed: Hour 3:30 A Day 9 Month 12 Year 1967

The Above well was plugged as follows:

RTD 4425 8 5/8 csg set at 274' cwc 185 sc.  
Gunned pits, circulated heavy mud, set cementing plug at 900' and displaced 100 sc cem.  
thru drill pipe. Heavy mud to 270' set cementing plug and displaced 25 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulla and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Mansur  
Well Plugging Supervisor

DATE 12/11/67  
INV. NO. 6873-4