

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-135 21 951-00-00

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name Palomino Petro.

Complete Address Box 18610 - Wichita, Ks

Lease Name Reisenacht. Well No. #1

Location C. SE. SW. Sec. 9 Twp. 17 Rge. 24 (East) (West)

County Ness. Total Depth 4435

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso, Casing Pulling.

Address Box 176, Chase Ks. License No. 683.

Operation Completed: Hour: 5:30 PM Day: 17 Month: Aug. Year: 19 81

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

KB. 2402 - SP. 368' of 8 1/8" cwe. 200 gx. 4 1/2" set  
@. 4433. w/175. Sx., Plug Back. 4336. Perf. 4270. to 74'  
Bottom Plug to 4200 w/sand & 5. sx, com. Com. Recovered  
2005' of 5 1/2" casing. Pumped down. S.P. 4 gx Hulla.  
15. gx Gel. 1. Sx Hulla. 70 gx Com. 50% - 4% Gel. 3% C.C.  
10 gx Gel. Release Plug. & 70 gx rem. 50% Poz. 4% Gel.  
3% C.C. Max. Pres. 700 lbs. Shut in Pres. 600 lbs.  
By Allied.

RECEIVED  
STATE CORPORATION COMMISSION

08-20-1981

I hereby certify that the above well was plugged as herein stated.

Signed: J. Maurin Schmidt  
Conservation Division  
Wichita, Kansas

9-25-81  
7446W