

15-135-21084-00-00

P

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

SEP 30 1975  
09-30-1975  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Okmar Oil Co.  
Complete Address 970 Fourth Financial Center, Wichita, Kansas  
Lease Name Tilley Well No. 1  
Location C SW SW Sec. 9 Twp. 17 Rge. (E) (W) 24  
County Ness Total Depth 4432'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Strata Drlg.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 10 P Day 23 Month 9 Year 1975

The above well was plugged as follows:

RTD 4432' 8 5/8 csg set 327' cwc 180 sk. Plg. Mat. 50-50 poz 6% total gel.  
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.  
Heavy mud to 300' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/30/75

INV. NO. 1988-W

Signed: B. C. Messer  
Well Plugging Supervisor