

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-35-20528-00-00

RECEIVED
STATE CORPORATION COMMISSION
01-28-1974
JAN 28 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thunderbird Drilling, Inc.

Complete Address P. O. Box 18407 Wichita, Kansas 67218

Lease Name Yost "C" Well No. 2

Location C SW SW Sec. 36 Twp. 17 Rge. (E) (W) 24

County Ness Total Depth 4412'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 11:30 A Day 23 Month 1 Year 1974

The above well was plugged as follows:

Total Depth 4412' 8 5/8 csg set at 355' cwe 259' sk.

5 1/2' csg set at 4410' ew 100 sk cem.

Filled 5 1/2' csg W/sd (4385-4412) dumped 5 sk cmt W/dump bailer. (4350-4385)

Cutoff and recovered 2703' of 5 1/2' csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/200 lbs hulls -70 sk 50-50 pez 6% gel-

10 sk gel & water -released 8 5/8 plug and pumped 50 sk 50-50 pez 6% gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo A. Massey
Well Plugging Supervisor

INVOICED

DATE 1/30/74

INV. NO. 8460-W