

15-8135-20603-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

05-01-1972

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

MAY 1 - 1972

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dunne -Gardner Petroleum, Inc & Resources Investment Corporation

Complete Address Suite 250, 200 W. Douglas, Wichita, Kansas

Lease Name Ummel Well No. 1

Location C NE NW Sec. 36 Twp. 17 Rge. (E) (W) 24

County Ness Total Depth 4484'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 2 P Day 27 Month 4 Year 1972

The above well was plugged as follows:

RTD 4484' 8 5/8 csg set at 327' cwc 200 sk. Cmt. Mat. 50-50 poz cmt W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 700' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 5-3-72

INV. NO. 5673-4