

RECEIVED
STATE CORPORATION COMMISSION
10-11-1972

KANSAS

Form CP-3
Rev. 6-4-68

CONSERVATION DIVISION
Wichita, Kansas

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-135-20690-00-00

Operator's Full Name Dane G. Hansen Trust
Complete Address Box 187 Logan, Kansas
Lease Name Depperschmidt Well No. 1
Location C SE SE Sec. 34 Twp. 17 Rge. (E) (W) 24
County Ness Total Depth 4440'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor C & G Drilling
Address Wichita, Kansas License No.
Operation Completed: Hour 7 P Day 9 Month 10 Year 1972

The above well was plugged as follows:

RTD 4440' 8 5/8 csg set at 320' cwc 250 sk. Cmt. Mat. 50-50 poz cmt W/6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Muesy
Well Plugging Supervisor

DATE 10/11/72
INV. NO. 6454-W