

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

FEB 11 1976

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name R. P. Nixon Operations
Complete Address Box 589, Russell, Kansas
Lease Name Desmarteau Well No. 1
Location SE NE SE Sec. 31 Twp. 11 Rge. (E) (W) 18
County Ellis Total Depth 3662'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Emphasis Drlg.
Address Russell, Kansas License No.
Operation Completed: Hour 8:30 P Day 8 Month 2 Year 1976

The above well was plugged as follows:

RTD 3662' 8 5/8 csg set 200' cwc 140 sk. Plg. Mat. 50-50 poz 2% total gel.
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.
Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *Leo Massey*
Well Plugging Supervisor

INVOICED

DATE 2-11-76

INV. NO. 2735-W