

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 1296

LOCATION SE NW NE

SEC. 31 TWP. 11 RGE. 18

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 4 Lease W. Johnson

Operator Shell Oil Co Address Great Bend, Kans

Field _____ County Ellis

Total Depth 3679 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1414' circulated with cement, 4 1/2" at 3629'.

P. B. by Shell to 3601', top Perforations at 3379'.

Plugged with chat to 3350', set 4 sax cement with dump bailer,

pulled 2350' 4 1/2", filled with mud to 250', set bridge and

15 sax cement, filled with mud to 35' and set 10 sax cement

to bottom cellar.

RECORDED

7-18-50

JUL 18 1950

PLUGGING
FILE SEC 31 T 11 R 18w
BOOK PAGE 12 LINE 6

J. Eddon
ST/ *J. Eddon* JUN 18 1950
District Conservation Agent

Date 7-16-50