

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Beacon Resources Corporation
Complete Address Suite 1000 Century Plaza, Wichita, Kansas
Lease Name Pfeifer Well No. 1
Location N/2 NE SW Sec. 31 Twp. 11 Rge. (E) (W) 18
County Ellis Total Depth 3697'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor E & B Drilling
Address Wichita, Kansas License No.
Operation Completed: Hour 10:15 P Day 18 Month 12 Year 1972

The above well was plugged as follows:

RTD 3697' 8 5/8 csg set at 240' cwc Cmt. Mat. "Hallib.-Light"
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/22/72
INV. NO. 6959-W

Signed: Leo J. Masser
Well Plugging Supervisor