


KANSAS


 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
 Administrator
 P. O. Box 17027
 Wichita, Kansas 67217

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 18 1972
 CONSERVATION DIVISION
 Wichita, Kansas

Operator's Full Name Hummon Oil Company
 Complete Address 6409 E. 14th St. Wichita, Kansas 67206
 Lease Name Pfeifer (SWD) Well No. 2
 Location S/2 SE SE Sec. 31 Twp. 11 Rge. (E) (W) 18
 County Ellis Total Depth 3676'
 Abandoned Oil Well Gas Well Input Well SWD Well XX D & A
 Other well as hereafter indicated
 Plugging Contractor Co. Tools by HOWCO
 Address License No.
 Operation Completed: Hour 1:30 P Day 16 Month 9 Year 1972

The above well was plugged as follows:

Total Depth 3676' 8 5/8 csg set at 248' cwc

5 1/2 csg set at 3676' cw 150 sk cmt.

5 1/2 csg PB & perf. (3286)

2-stage collar at 1550' cwc to surface. No pipe recovered.

Pumped down 5 1/2 csg with 50 sk cmt -25 sk gel & water W/300 lbs hulls -released

5 1/2 plug and pumped 85 sk cmt. PP 300 lbs. SIP 150 lbs.

Checked annulus with 800 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/18/72

INV. NO. 6330-W

Signed: Leo J. Massey
 Well Plugging Supervisor