

¹⁰
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 30 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morganstern Specter

Complete Address: Russell, Kans

Lease Name Wasinger Well No. 1

Location Approx 150' S of SE SW NE Sec. 20 Twp. 11 Rge. (E) (W) 18

County Ellis Total Depth 3621

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ralph Lynch

Address: Great Bend, Kans License No. 457

Operation Completed: Hour 6PM Day 28 Month 10 Year 64

The Above well was plugged as follows:

8 5/8" 172' circulated with cement - 5 1/2" 3618' with 100 sax cement.

Sand to 3000', set 5 sax cement with dump bailer - pulled 2990' 5 1/2" to
600' circulated hole with heavy gel mud through 5 1/2" at 300' - displaced
20 sax cement through 5 1/2" at 550', heavy mud to 250', displaced 20 sax
cement through 5 1/2" at 250', heavy mud to 35', cement to 0'

Mudding and cementing by Lynch Company pump truck.

I hereby certify that the above well was plugged as herein stated.

DATE 10/30/64

INV. NO. 49-W

Signed: [Signature]
Well Plugging Supervisor